



**The Corporation of the Municipality of Wawa
Staff Monthly Report**

Office of Infrastructure Services

Prepared For: Corporate Planning Committee Meeting	Report No.: CS 2018-12
Agenda Date: September 11, 2018	File No.: 9.40.4

Preamble

The following report is based on items concerning the Municipality of Wawa that have been directed by the Infrastructure Services Department. This information is for the months of June – August 2018.

Summer Operations

During the months of June – August 2018, Infrastructure Services Department focus was on maintaining road conditions through sweeping, dust control, painting, pot hole repairs, grading, applying more granular 'A', cutting of grass and brushing of bushes.

Water & Sewer

THM Study

Walkerton Clean Water Centre has been completing studies in their lab to monitor effectiveness of coagulants using Wawa's lakes water. This process will help identify how much of coagulant should be used and which type reacts best for our treatment facility. A full report is expected end of Oct. 2018.

Operations

Routine flushing of certain sewers was performed including monthly maintenance at the Sewage Treatment Plant and Water Treatment Plant.

Respectfully Submitted By:

Prepared By:

Cory Stainthorpe
Director of Infrastructure Services

Cemetery

A water break occurred at the lateral to supply the cemetery; due to delay in parts for the repair this limited IS staff ability to water the grounds this year. Everything is now repaired and operating.

Beautification of the cemetery was a main focus in 2018, roadways were replaced with new granular 'A' and over grown or dead trees were removed and soil/seed placed.

Capital

As progress is made on each project it will be included in reports to Council.

Landfill Expansion

Kresin Engineering continues to work on environmental assessment and impacts regarding landfill expansion. Discussion is occurring with the Ministry on location for expansion and finalizing the CAZ for land closer to the River and increase the amount of monitoring wells on site.

In fall 2018 an open house session will be advertised and held in Wawa to discuss where the expansion process is at and future direction.

New Street Lights

Contractor has completed the installation of several street lights along Tamarack Avenue towards Government Road including additional lights on each off street that connects to Tamarack.

API is to finish the connection of these street lights by end of October 2018.

Garage Hoist

The new garage hoist was installed as per capital budget.

Library Floor

The new library floor has been installed with some minor work remaining with the upstairs office which will be completed before end of October 2018.

Admin Fleet Upgrade

All fleet have been replaced as outlined in the report for Capital 2018. There is still one (1) vehicle that is being shipped. The last vehicle is expected mid October 2018.

Sewage Lagoon Building Upgrades

Both Alum pumps have been installed; building upgrades for the roof have also been completed.

Lower Government Road

Lower Government Road has some shoulder work to be completed and a section of Government Lane. Provost is still expected to complete in 2018.

Pinewood Drive

Pinewood Drive has some outstanding shoulder work to be completed from 2017 and addition of drainage in two identified locations. This work is to be completed in 2018, though due to timelines and contractor availability some work may have to be completed in 2019.

MRV Water Tower Exterior Lining

Landmark is has completed the exterior lining.

Magpie Fuel System

Upon review of RFP for this project, 3 bids were received; it was determined to cancel this process. The bid that was within budget had a poor evaluation from management staff, other bidders exceeded project budget.

Due to a study being conducted on 26 Magpie road (Infrastructure services building), a decision was made to delay project until 2019 after the IS structure is reviewed.

Toronto Avenue Sewer Reconstruct

Toronto Avenue has a potable water system set up for servicing residents while the water main is shut off for excavation.

Provost is excavating the area and replacing the storm sewer, sanitary sewer and water mains in 2018. The remaining work for resurfacing (asphalt, curbs, and sidewalks) will be completed in 2019.

Attachments

There are no attachments with this report.